

DIGBETH LOC. STUDIOS



BBC Studioworks

Studio Rules for Productions – Digbeth Loc. Studios

Health & Safety Arrangements

HEALTH & SAFETY ARRANGEMENTS	2
1. INTRODUCTION	2
2. EVENT MANAGEMENT	2
3. RISK ASSESSMENT	2
4. DESIGN & DESIGNERS RISK ASSESSMENT	3
5. ACCESS FOR DISABLED PEOPLE	3
6. LIGHTING DESIGN, ELECTRICAL AND TECHNICAL RIG	3
7. USE OF CONTRACTORS / FREELANCE STAFF	3
8. PERMIT TO WORK AND PRODUCTION PERMISSION PERMIT	4
9. EXTERNAL FILMING PERMITS	4
10. MATERIALS AND HAZARDOUS SUBSTANCES	4
11. GLASS	5
12. WATER AS A PROP OR EFFECT	5
13. SMOKE, HAZE OR OIL MIST EFFECTS	5
14. USE OF WEAPONS	5
15. SITE INDUCTION	6
16. MEANS OF ESCAPE.....	6
17. NOISE IN THE STUDIO.....	6
18. WORKING AT HEIGHT.....	6
19. MOBILE ACCESS PLATFORMS	7
20. WORKSHOPS	7
21. VIDEO WALLS.....	7
22. CAMERA AND SOUND OPERATIONS	8
23. ELECTRICAL EQUIPMENT.....	8
24. WORK EQUIPMENT.....	8
25. LIFTING EQUIPMENT	8
26. FLOOR LOADING.....	7
27. TOW TRUCKS AND FORK LIFTS	9
28. CABLE MANAGEMENT	9
29. STUDIO FIRE LANES.....	9
30. ACCIDENT/INCIDENT/NEAR MISS REPORTING	9
31. FIRST AID ARRANGEMENTS	9

HEALTH & SAFETY ARRANGEMENTS

1. Introduction

This document outlines and identifies the health and safety management arrangements for visiting productions when hiring studio space from BBC Studioworks. A number of policies and procedures have been written and implemented by BBC Studioworks that are referenced within this document when necessary.

If Productions have any questions after reading this document, they should refer the matter to the Resource Manager.

2. Event Management

For some projects in the stages and external areas, it may be necessary for the production to employ an event manager to control all aspects of the production/event and act as the main point of contact for all planning and operational activities. Event managers should be competent in the role, with experience and qualifications relevant to the type of event being implemented. Productions are advised to assess event manager experience and relevance using the SKATE acronym (Skills, Knowledge, Attitude, Training and Experience) where necessary.

3. Risk Assessment

The Producer must provide a production risk assessment to the Studio Facilities Manager. Where contractors or freelance staff are engaged, it is the responsibility of the Producer to ensure they are competent to carry out the task. These contractors must provide a risk assessment and method statement and communicate their findings to the production and be included in the production risk assessment.

The production risk assessment must cover arrangements for first aid and fire, and if applicable, audiences, guests, contributors and children as well as direct production hazards such as smoke/visual effects.

4. Design & Designers Risk Assessment

All scenery constructed for use in Studioworks spaces must be designed and constructed so as to eliminate potential risks which can arise during the setting, movement, handling and striking phases of production.

The Designer must provide in advance of setting, a risk assessment including the fire protection arrangements to both the Production and Studio Facilities Manager. The designers may have specific duties under the construction (design and management) regulations, depending on the build framework.

For specific details on fire safety requirements for props and scenery at Studioworks sites please refer to [Fire-Safety-Props-and-Scenery](#)

5. Access for Disabled People

The Producer as part of the risk assessment must ensure adequate provisions are available for disabled people. This would include the access and egress into the Studio, ramps, seating, hearing enhancement system, interpreter (signer) and evacuation procedures where necessary.

Access provision should be discussed at the planning meeting. Whilst engaging with a handling contractor, it is essential that the production discuss arrangements that are/are not possible for a personal emergency evacuation procedure.

6. Lighting Design, Electrical and Technical Rig

An important part of the production process is the rigging of the lighting equipment. This phase of the production process must be carefully planned to ensure any hazardous activities are planned out. A full risk assessment must be provided by a competent person e.g. a Lighting Director.

The de-rig phase of the production must also be carefully planned, to ensure that activities taking place simultaneously do not create hazardous situations. The final plans for these phases of the production must be ready for discussion at the planning meetings.

7. Use of Contractors / Freelance Staff

Contractors or freelance staff must be trained, experienced and competent to carry out the task intended safely. The level of competence will depend on the complexity of the activity. Visiting productions should highlight all high-risk activities e.g. stunts, SFX at the Planning Meeting. The contractor/freelancer carrying out the high-risk activity must supply risk assessments.

8. Permit to work and Production Permission Permit

Permits are required for certain types of works in/around the studios undertaken by third party contractors and construction contractors (during construction phase).

There must be a thorough risk assessment and method statement in place before commencement; supported by a suitable plan of work outlining the hazards, the methods by which they can be avoided and details of any residual risks that may occur.

If necessary, equipment will be inspected by BBC Studioworks management before use, as well as checks to ensure the correct PPE is used where required.

Permit to Work system are generally used for works that typically involve:

- Asbestos Containing Material (ACMs), or locations close to ACMs;
- Confined Space;
- Electrical H/LV;
- Hot Works;
- Lone Working;
- Working on Studio Grids;
- Roof Work
- Fire Alarm Smoke Isolations

9. External Filming permits

For productions wishing to film on the external areas of site, they must submit a filming permit request form along with risk assessments to the Studio Facilities Manager. This is to ensure coordination of activities on site, that they are carried out in a suitable and safe location and where appropriate, the local authorities and neighbours are made aware of any high risk and noisy activities that may cause concern such as use of explosives or weaponry.

10. Materials and Hazardous Substances

Materials and substances brought into the Studio must be safe to use and not introduce additional hazards. Where a substance is deemed hazardous under COSHH (The Control of Substances Hazardous to Health Regulations 2002), a COSHH assessment must be supplied and attached to the risk assessment.

For environmental purposes, all materials and substances must be disposed of correctly. Productions should check with the Studio Facilities Manager for disposal procedures.

11. Glass

Use of glass in the studio as prop, effect or scenery needs to be authorized by BBC Studioworks management. Sets requiring glass elements, such as windows, should use industry standard substitutes or equivalent. Where glass is required on set, plans and risk assessments must be submitted and approved prior to use. Signage must be installed at all access points to the studio to make staff and visitors aware real glass is on set.

The producer must ensure that the build and derig is suitably planned to ensure the risk of injury from the presence of glass is reduced sufficiently.

12. Water as a prop or effect

Where water is to be used as a prop or effect, plans and a risk assessment must be provided by the person introducing the effect. This must include the type of prop or effect to be used, the competence of the operator, how this will be managed.

The producer must be aware of their responsibilities regarding the safe use of water and for the purposes of the control of legionella, may be identified as the responsible person. Installations that are in use for extended periods of time, or from equipment not used regularly may require testing and treating. This must be planned in advance of the production going live, with scheduled times identified for testing and treating where necessary.

13. Smoke, Haze or Oil Mist Effects

Where smoke, oil mist or haze is to be used, a risk assessment must be provided by the person introducing the effect. This must include the type of substance to be used, the competence of the operator, level of exposure, how this will be monitored, and whether an audience will be present. Signage and prerecord notification should be made to audience members via floor manager, warm up artist/compare and/or signage leading into the studio and prior to use.

14. Use of Weapons

The use of armoury and weapons in the studio as a prop or effect is subject to a risk assessment and method statement. Method statements, plans and risk assessments must be submitted and agreed prior to use. The producer must ensure details are provided to the Resource Manager relating to the armorer that is engaged and arrangements for transportation/storage of weapons.

The use of discharge weapons (blank firing guns) must be raised no less than 28 days to the Studio Facilities Manager prior to arrival at the studio.

15. Site Induction

All persons working on site should complete the site induction prior to their arrival. An ID card will only be issued once the inductee has signed the link to accept that they have read and understood the terms and conditions for working safely on site.

BBC Studioworks reserves the right to remove anyone from site who is found to be in breach of the site health and safety rules.

16. Means of Escape

A clear route must be maintained at all times to emergency exits situated to the rear of the studio and rear of the stage. Rigging and equipment set-up must take account of this.

17. Noise in the Studio

Vising productions and all commissioning managers involved must ensure that the standards set out in the BBC Studioworks noise and sound policy document are met.

The need for a noise risk assessment should normally be identified at the planning stages of any production and considered as part of the programme or resources risk assessment. This should identify the people who might require health surveillance, a procedure for recording assessment and any action taken.

In brief; If an activity is over 80dB(A) a noise assessment will have to be undertaken to help control the sound level. Further guidance can be found in the noise and sound policy document. Based on the level of exposure, it may be necessary for the production to implement a noise management procedure.

18. Working at Height

Any requirement for persons to work at height must be covered by a risk assessment and the necessary control measures put in place to reduce any risk of them falling or dropping objects. Clients and users of high level facilities are responsible for ensuring the safe system of work is in place and operated at all times. All methods to eliminate work at height must be considered.

19. Suspended Scenery/Roof Loading

Visiting productions are responsible for the safe construction, dressing and suspension of scenery. All of which should be appropriately risk assessed and managed. All scenery that is suspended must be secured by irons (or other fixings) that are within a testing and inspection regime, as required by the Lifting Operations and Lifting Equipment Regulations with the safe working limit clearly marked. Hanging irons must be correctly secured onto each flat/set element and checked prior to lift and suspension.

Scenic elements that include electrical components or installation must be designed and installed to comply with BS7909 and BS7671. The work of fixing wiring and electrical equipment to scenery should be undertaken by a competent and qualified electrician. Each separate piece of scenery with electrical equipment attached or with working practical's, should have evidence of having passed a formal visual inspection and electrical test such as a Portable Appliance Test. Evidence of this inspection and test should be provided to BBC Studioworks.

The stage roofs are at maximum load bearing so must not be used for suspending scenery. Nothing should be attached to the roof structure, even for lateral support of the stages without consulting the Studio Facilities Manager.

20. Floor Loading

Any ground supported structure or equipment must not exceed the maximum floor loading weight limit. Please contact the Studio Facilities Manager for further information.

21. Mobile Access Platforms

The use of MEWPS is strictly restricted to persons authorised to operate the equipment. Operators will have available their photographic license specific for the platform they intend to operate. Operators wishing to operate 'cherry pickers' must have the most appropriate harness on at all times. The harness must be free from damage, subject to user checks and tightened specifically to the user. Any work at height with a harness is subject to a suitable rescue plan being in place by the operator/employer.

22. Workshops

Only those authorized by BBC Studioworks may have access to the workshops. All hot works require a PTW to be issued prior to commencement. Soldering is only allowed to take place in controlled conditions with hot work procedures/permit, and adequate local exhaust ventilation.

23. Video Walls

Video walls must be designed and constructed with regard to the intended usage including factors such as intended mobility, height, eccentric load etc.

Where possible the use of "projection type" monitors (LCD screens) must be encouraged as the centre of gravity is more central thus making the wall more stable. Design features must include adequate counterbalancing featured as an integral part of the set. The video wall itself must be securely attached to a secure structure where possible. All screens within a video wall must be bonded to each other and to the main structure to ensure the stability.

Persons working at height will be competent to do so and will have received work at height training, this must be covered by a risk assessment and the necessary control measures put in place.

24. Camera and Sound Operations

Risk assessments must be carried out to cover Camera and Sound operations, these risk assessments must be available to view at any time at the request of the Studio Facilities Manager.

25. Electrical Equipment

All electrical equipment used in the Studio must have a portable appliance test (PAT) and have a current test label displayed. Where there is no test label, an electrical test must be carried out, and if the equipment fails the test, it must be taken out of service. Where equipment is to be used in the Studio from an outside source, it must be PAT tested prior to use.

All electrical equipment and electrical distribution must be rigged and used in a safe manner. This includes correctly rated equipment, connected in the correct manner.

Cabling must be covered or ramped when trailed across walkways/fire lanes and securely bonded if flown.

26. Work Equipment

Any work equipment brought into and used in the Studio must be fit for its intended use, have all relevant test labels attached and any guards fitted and used.

The operator of any work equipment must be competent to use it safely and have been trained to do so. All work equipment must be of sound construction and free from defect.

As appropriate, noise levels should be considered.

27. Lifting equipment

All lifting equipment must have a written scheme of examination by a competent person. Check examinations must be carried out in accordance with the scheme.

Lifting equipment must only be used by a competent person as verified in the scheme and associated risk assessment.

Lifting equipment selected for the job must be of the correct type and be designed and constructed for that particular job.

The safe working load should be marked on all component parts and not exceeded.

All equipment suspended overhead, such as lighting fixings must have a secondary rigging point, sometimes referred to as the 'safety', to ensure the risk of injury is greatly reduced should the primary rigging point fail.

28. Tow Trucks and Fork Lifts

Drivers must be fully competent and have received training that meets the Approved Code of Practice L117 – Rider – Operated Lift Trucks Operator Training and instructed on the hazards, risks and procedures for FLT operation at BBC Studioworks prior to being authorised to operate the trucks on programme related operations.

29. Cable Management

All cables used in the Studio must be ramped, matted or flown to reduce trip hazards. Large coils of main carrying cabling should be avoided. Coils should only be permitted at certain times and as a result must be suitably placed away from emergency walkways, placed into a figure of 8 coil.

30. Studio Fire Lanes

Fire exit signs must be lit, clearly visible and not obstructed. Where scenery obstructs fire exit signage, temporary signs must be used.

All cables which cross the fire lane must be ramped or flown to reduce trip hazards. Fire lanes must never be blocked by people, props or equipment. The only exception is manned equipment which can be easily moved. This must be on a risk assessment basis with all controls for this activity recorded.

31. Accident/Incident/Near Miss Reporting

If an accident or incident occurs on site, the Studio Facilities Manager must be informed in the following circumstances:

- Any serious accidents/near misses that are RIDDOR (HSE) reportable
- When an ambulance is called
- Where an accident/near miss is due to an issue with the site facilities or services

32. First Aid Arrangements

This must be determined by the Producer and should be based on the level of risk identified and the number of people present in the Stages.